


Nogging Schedule 2201 - 2425 High

Suitable for Precision GTS-2, Genius GTS - 3 or Smart Pro GTS-4



All Nogs must be centred

Please contact us for alternative motor requirements

Refer to Quote for Weight Estimate or get in touch

NOTE: Doors over 150kg require extra track fixings for X at 1170mm

Please consult your Rep for doors over 6000w or 180kg

ALL DOORS OVER
200KG SHOULD BE
CHECKED WITH
YOUR STRUCTURAL
ENGINEER TO
ENSURE ADEQUATE
STRENGTH

BOOK INSTALL - 09 638 9474

Call us at least 2 weeks before the requested installation date to book install.

To avoid a non-install charge (\$175+GST+Travel*) please ensure;

- 1) Lining on ceiling walls are complete
- 2) Garage is clear 4m back from the door
- 3) Clear access on garage driveway
- 4) Access to powder supply in garage
- 5) All nogs ready per this sheet
- 6) We need minimum 48 hours to change the install date once booked

7000	(40mm)
	Rebate - to be taken off finish (Eg Architrave) Depth 25mm Where possible, solid fixing across lintel is preferred
	Please notify us of any Architrave additions / Alterations

Measurements after Gib is installed			
	Standard	Low	
Headroom	350mm	200mm	
Sideroom	155mm	110mm+	
Backspace to Motor	Door Height + 900mm	Door Height + 1100mm	
If Continuity had a manual that have been decreased			

If Coving is being used, the headroom is taken from the bottom of the coving

Any questions call your Sales Representative or Prestige Office on 09 638 9474

\$3 per km over 20km from Prestige Factory (Penrose) POA for Waiheke or outside of Auckland